STRIP FOOTING SCHEDULE
2,500 P.S.F. BEARING CAPACITY

MK	SIZE		REINFORCEMENT	
	WIDTH (INCHES)	DEPTH (INCHES)	LONGITUDINAL	TRANSVERSE
SF2.0	24"	12"	(3) #5 BARS	#5 BARS 36" O.C.

NOTES:
1. STRIP FOOTING SHALL BE NORMAL WEIGHT CONCRETE (f'c = 4,000 psi AT 28 DAYS).
2. MINIMUM CONCRETE COVER PROTECTION FOR REINFORCEMENT BARS SHALL CONFORM WITH THE "MINIMUM CONCRETE COVER FOR REINFORCING BAR" TABLE PROVIDED. (SEE ACI 318-19 SECTION 7.7 FOR CONDITIONS NOT NOTED)

FOOTING SCHEDULE
2,500 P.S.F. BEARING CAPACITY.

MK	SIZE				
	LENGTH	WIDTH	DEPTH (INCHES)	BOTT. REINF. EW-EACH WAY L-LONG S-SHORT	REMARKS
MF1	16'-0"	11'-2"	12"	#5 BARS AT 12" O.C. (E.W.) (TOP & BOTTOM)	

NOTES:
1. SPREAD FOOTING SHALL BE NORMAL WEIGHT CONCRETE (f'c = 4,000 psi AT 28 DAYS).
2. MINIMUM CONCRETE COVER PROTECTION FOR REINFORCEMENT BARS SHALL CONFORM WITH THE "MINIMUM CONCRETE COVER FOR REINFORCING BAR" TABLE PROVIDED. (SEE ACI 318-19 SECTION 7.7 FOR CONDITIONS NOT NOTED)

SLAB ON GRADE CONSTRUCTION SCHEDULE

MARK	AREA	f'c (psi)	THICKNESS	REINFORCEMENT
①	INT. SOG	4,000	5"	WWF 6x6-W1.4xW1.4 (SEE NOTE 5)


NOTES:
1. ① INDICATES CONCRETE SLAB ON GRADE PLACED OVER A VAPOR BARRIER ON 6" OF CRUSHED STONE
2. MINIMUM CONCRETE COVER PROTECTION FOR REINFORCEMENT BARS SHALL CONFORM WITH THE "MINIMUM CONCRETE COVER FOR REINFORCING BAR" TABLE PROVIDED. (SEE ACI 318 SECTION 7.7 FOR CONDITIONS NOT NOTED).
3. ANY EXTERIOR STAIRS, RAMPS, OR ELEVATED PLATFORMS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 5000PSI CONCRETE.
4. CONTROL JOINTS IN SLAB ON GRADE SHALL BE LOCATED AND SPACED IN ACCORDANCE WITH TYPICAL CONTROL JOINT DETAIL ON S502.
5. CONTRACTOR MAY SUBSTITUTE 1.5 POUNDS OF FIBROUS REINFORCEMENT PER CUBIC YARD OF CONCRETE IN LIEU OF WWF.
6. REFERENCE TYPICAL CONCRETE SLAB DETAILS ON S502 FOR ADDITIONAL INFORMATION.

STEEL COLUMN SCHEDULE

MK	COLUMN SIZE
C1	HSS6X6X1/4

BASE PLATE SCHEDULE

MK	LENGTH	WIDTH	THICKNESS	ANCHOR BOLTS	EMBEDMENT
BP1	12"	7"	1/2"	(2) 3/4" DIA. HY-270 + HAS V-36	6"



BP1

CONCRETE WALL SCHEDULE

MK	THICKNESS	NO OF CURTAINS	VERTICAL REINF.	HORIZONTAL REINF.	REMARKS
CW12.1	1'-0"	2	#5 BARS AT 12" O.C.	#5 BARS AT 12" O.C.	

NOTES:
1. ALL CONCRETE WALLS SHALL BE 4,000PSI CONCRETE.
2. WALL THICKNESS AND REINFORCEMENT SHALL APPLY TO ALL LEVEL OF WALL ABOVE POINT OF DESIGNATION OR UNTIL NEXT WALL DESIGNATION.
3. REFERENCE TYPICAL CONCRETE WALL CONSTRUCTION DETAILS ON S516 FOR ADDITIONAL INFORMATION.
4. (C) - CENTERED / (OF) - OUTSIDE FACE / (IF) - INSIDE FACE.

MASONRY WALL SCHEDULE

MK	THICKNESS	VERTICAL REINF.	HORIZONTAL REINF.	REMARKS
MW8.1	8"♳	#5 BARS AT 24" O.C.	(SEE NOTE 3)	

NOTES:
1. MASONRY WALLS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF f'm = 2000psi U.N.O.. FILL ALL REINFORCED CELLS SOLID WITH 3000psi GROUT.
2. WALL THICKNESS AND REINFORCEMENT SHALL APPLY TO ALL LEVELS OF WALL ABOVE POINT OF DESIGNATION OR UNTIL NEXT WALL DESIGNATION.
3. PROVIDE HORIZ. REINFORCEMENT (9 ga. GALVANIZED TRUSS TYPE) AT 16" O.C.
4. PROVIDE 16" DEEP BOND BEAMS AT EACH FLOOR LEVEL w/ (2) #5 BARS CONTINUOUS. PROVIDE 8" DEEP BOND BEAMS BETWEEN FLOORS WHERE WALL IS GREATER THAN 10ft w/ (1) #5 BARS CONTINUOUS. ALL BOND BEAMS SHALL HAVE KNOCK OUT BLOCKS AND SHALL BE FILLED SOLID WITH 3000PSI GROUT, REFERENCE TYPICAL DETAIL ON S531 FOR ADDITIONAL INFORMATION.
5. CONTRACTOR SHALL MAINTAIN RUNNING BOND THROUGHOUT WALLS AND CORNERS.
6. REFERENCE FRAMING PLANS FOR LINTELS, STEEL BEAMS, BEARING PLATES, AND LEDGER CONNECTION LOCATIONS.
7. REFERENCE TYPICAL CONCRETE MASONRY WALL CONSTRUCTION DETAILS ON S531 FOR ADDITIONAL INFORMATION.

LOAD BEARING WALL LINTEL SCHEDULE

MK	TYPE	SIZE (W)x(H) (IN)	REINFORCEMENT	REMARKS
ML1	MASONRY	8x8	(1) #5 BARS	N/A
SL1	STEEL	W8x15	N/A	+3/8" THICK STEEL PLATE

NOTES:
1. REFERENCE S531 FOR ALL APPLICABLE TYPICAL DETAILS.

4,000 PSI NORMAL WEIGHT

BAR SIZE	db	LAP CLASS	TOP BARS CASE 1	TOP BARS CASE 2	OTHER BARS CASE 1	OTHER BARS CASE 2
#3	.375	EMBEDMENT (A)	19	28	15	22
		SPLICE (B)	24	36	19	28
#4	.50	EMBEDMENT (A)	25	37	19	29
		SPLICE (B)	32	48	25	37
#5	.625	EMBEDMENT (A)	31	47	24	36
		SPLICE (B)	40	60	31	47
#6	.75	EMBEDMENT (A)	37	56	29	43
		SPLICE (B)	48	72	37	56
#7	.875	EMBEDMENT (A)	54	81	42	63
		SPLICE (B)	70	106	54	81
#8	1.0	EMBEDMENT (A)	62	93	48	71
		SPLICE (B)	80	121	62	93

NOTES:
1. TENSION DEVELOPMENT LENGTHS AND LAP SPLICE LENGTHS ARE CALCULATED PER ACI 318-19, SECTIONS 25.4.2.2 AND 25.5.2, RESPECTIVELY.
2. CASES 1 & 2 WHICH DEPEND ON THE TYPE OF STRUCTURAL ELEMENT, CONCRETE COVER AND THE CENTER-TO-CENTER SPACING OF BARS ARE DEFINED IN THE TABLE ON THE RIGHT.
3. LAP SPLICE LENGTHS ARE MULTIPES OF TENSION DEVELOPMENT LENGTHS: CLASS A - 1.0 AND CLASS B - 1.3 (ACI 25.5.2.1). VALUES FOR BARS IN BEAMS OR COLUMNS ARE BASED ON TRANSVERSE REINFORCEMENT MEETING MINIMUM REQUIREMENTS FOR STIRRUPS IN ACI 9.6.3 AND 9.6.4 OR MEETING THE REQUIREMENTS OF ACI 10.6.2 AND ARE BASED ON MINIMUM COVER SPECIFIED IN ACI 20.6.1.
4. CONDITIONS WHICH REQUIRE CASE 1 SPLICE LENGTHS SHOULD BE AVOIDED IF AT ALL POSSIBLE FOR THE LARGER BAR SIZES. THESE ORDINARILY LONG LENGTHS PRESENT POSSIBLE CONSTRUCTABILITY PROBLEMS DUE TO PLACING CONGESTION ETC.
5. TOP BARS ARE HORIZONTAL WITH MORE THAN 12 IN. OF FRESH CONCRETE CAST BELOW THE BARS.

STRUCTURAL ELEMENT	CONCRETE COVER	CASE ACCORDING TO CENTER-TO-CENTER BAR SPACING ≤ 2db	> 2db < 3db	> 3db
BEAMS, COLUMNS, AND LAYER OF WALLS OR SLABS.	≤ db	2	2	2
	> db	2	1	1
ALL OTHERS	≤ db	2	2	2
	> db	2	2	1


NORMAL WEIGHT CONCRETE STRENGTH	DEVELOPMENT LENGTH	LAP SPLICE LENGTH
3,000 PSI	22 db	30 db ≥ 12"
4,000 PSI	19 db	30 db ≥ 12"
5,000 PSI	18 db	30 db ≥ 12"
6,000 PSI	17 db	30 db > 12"

COMPRESSION DEVELOPMENT AND LAP SPLICE LENGTHS

NORMAL WEIGHT CONCRETE STRENGTH	BASIC HOOK DEVELOPMENT LENGTH
3,000 PSI	22 db
4,000 PSI	19 db
5,000 PSI	17 db

STANDARD HOOKED BAR TENSION DEVELOPMENT LENGTHS

1. WHEN COVERAGE REQUIREMENTS SHOWN IN DETAILS ARE MET, BASIC HOOK DEVELOPMENT LENGTH MAY BE MULTIPLIED BY 0.7.



REINFORCING DEVELOPMENT LENGTH AND LAP SPLICE SCHEDULE

MASONRY REINFORCEMENT LAP SPLICE SCHEDULE (f'm=2,000psi)

BAR SIZE	6in WALL	8in WALL	10in WALL	12in WALL
#3	12"	12"	12"	12"
#4	17"	13"	12"	12"
#5	27"	20"	15"	13"
#6	53"	37"	29"	24"
#7	-	52"	40"	33"
#8	-	72"	61"	50"
#9	-	-	73"	64"

RISE | FL
architecture

ARCHITECT:
NYC OFFICE:
241 37TH STREET, SUITE 440
BROOKLYN, NEW YORK 11232
JEFF AKERMAN, RA
JEFF@RISEARCHITECTURE.COM
516-249-3746
NJ OFFICE:
36 AIRPORT RD SUITE 402
LAKEWOOD, NJ 08701
SHIMON GREENEBAUM, RA
SHIMON@RISEARCHITECTURE.COM
908-674-8717
FL OFFICE:
210 N UNIVERSITY DR SUITE 210
CORAL SPRINGS, FL 33071
SHIMON GREENEBAUM, RA
SHIMON@RISEARCHITECTURE.COM
908-674-8717
STRUCTURAL CONSULTANT:
JT ENGINEERING
BUILDING SOLUTIONS
1321 BRUNSWICK AVE.
Lawrence, NJ 08648
P: 609.303.0236
F: 609.303.0237
www.jt-pe.com
MEP CONSULTANT:
CIVIL CONSULTANT:

REVISIONS:

NO.	DATE	DESCRIPTION
1	12/13/23	PERMIT

CLIENT:

PROJECT NAME / LOCATION:
Okeechobee (Mikvah)
FL-78 & Access Road
Okeechobee, Florida, 34978

DRAWING TITLE:
SCHEDULES

EXAMINER'S SIGNATURE:

PROFESSIONAL SEAL:
Jason Tarantino
Digitally signed by Jason Tarantino
Date: 2024.04.19 12:42:01 -04'00'
JASON C. TARANTINO
FL LIC. NO.
PE 94381

SCALE: AS NOTED
DATE:
PROJECT NO. 2318_06

DRAWING NO.
S005

BARCODE

THE GENERAL CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND REPORT ALL ERRORS AND OMISSIONS TO THE ARCHITECTS. DO NOT SCALE DRAWING. THE DRAWING SHALL NOT BE USED UNTIL SIGNED BY CONSULTANTS.

12/13/2023 12:34:40 PM